

AMENDMENTS TO THE CLAIMS:

This listing of claims will replace all prior versions, and listings, of claims in the application:

Listing of Claims:

1. (Currently Amended) Method for installing a machine unit foundations (1) and/or rolling stands (2) in an existing production line of a hot rolling mill ~~and/or for putting them into service in such plants,~~ comprising the steps of:

prefabricating a ~~where the machine foundation (1) is prefabricated, and required or interacting;~~

assembling the machine units unit comprising the machine foundation (1) and a rolling stand mounted on the machine foundation ~~are prefabricated and preassembled or assembled on site next to the production line (4) of the hot rolling mill, whereupon these machine units are inserted; and~~

inserting the machine unit into the production line (4) as a completely functional complete modular unit, wherein the step of assembling includes constructing the machine unit as a complete modular unit including the machine foundation block (1), wherein all the associated drive elements, control elements, fastening elements, as well as pipes, cables, and other pieces of equipment

necessary for operation ~~are installed or assembled on the machine/foundation block before insertion into the production line (4),~~ wherein the preassembled installation is subjected to a preliminary test run on site before it is inserted into the production line (4).

2. (Canceled)

3. (Currently amended) Method according to Claim 1, wherein the machine foundation ~~block~~ (1) with the completely assembled and operationally ready rolling stand machine unit/rolling stands (2) is moved into place along at least two displacement tracks (5).

4. (Previously presented) Method according to Claim 3, wherein the displacement is carried out in steps alternating between a left displacement axis and a right displacement axis.

5. (Currently amended) Method according to Claim 3, wherein the machine foundation ~~block~~ (1) to be displaced is raised; slideways are inserted between the machine foundation ~~block~~ (1) and the displacement tracks (5); and the machine

foundation ~~block~~ (1) is displaced and then lowered after reaching its final position.

6. (Currently amended) Method according to Claim 5, wherein pairs of intercommunicating double presses are used to raise and lower the machine foundation ~~block~~ (1).

7. (Currently amended) Method according to Claim 6, wherein the presses for raising the machine foundation ~~block~~ (1) are supported on lifting points / lifting surfaces (9, 10, 11) embedded in the displacement tracks (5).

8. (Currently amended) Method according to Claim 6, wherein the presses for lowering the machine foundation ~~block~~ (1) in the final position are supported on lifting points / lifting surfaces embedded in the displacement tracks (5).

9. (Currently amended) Method according to Claim 5, wherein the machine foundation ~~block~~ (1) is horizontally aligned in the final position on the basis of reference marks on the rolling stand axes.

10. (Currently amended) Method according to Claim 5, wherein the machine foundation ~~block~~ (1) is vertically aligned in the final position on the basis of reference marks.

11. (Currently amended) Method according to Claim 5, wherein the machine foundation ~~block~~ (1) is finely adjusted around its transverse axis.

12. (Previously presented) Method according to Claim 1, wherein the foundations of a roll-changing area are at least partially constructed and installed as prefabricated reinforced concrete structures.

13. (Canceled).

14. (Currently amended) Method according to Claim 1, wherein the machine foundations are partially or completely constructed as prefabricated reinforced concrete structural elements in the assembly area of the machine foundation ~~block~~ (1) to be displaced, so that they can later be used as a base for new machine foundations.